Land Issues in India

India: Socio-Economic Indicators

- One-fifth of world's poor live in India – the largest for any country.
- India has one-fourth (208 million) of world's 800 million under-nourished people.
- Child malnutrition is the world's highest.
- Human Development Index: 119 of 169 countries.
- GDP growth rate: +7% over 3 years.

Land Distribution & Ownership

- India is 70% rural with high dependence on land: agriculture, fisheries and forests.
- 83% of farmers are small farmers <2 hectares.
- Small farmers produce 41% of country's food grains.
- 60% of cultivable land owned by 10% of population.

Land Distribution & Ownership

- Unequal ownership of land – root cause of poverty & hunger.
- Landless and 'near-landless' ~ 220 million people.
- 90% of landless poor are Scheduled Castes (*Dalits*) & Scheduled Tribes (indigenous peoples).
- Majority work as agricultural labour and sharecroppers.
- Access to land is a key determinant of food security and livelihood protection.

Women & Land

- Rural women depend greatly on land for subsistence.
- Perform > 50% of all agricultural work.
- 35% of rural households are women-headed, but less than 2% women hold titles to land.
- Migration of men to urban areas – resulting in ‘feminisation of agriculture.’
- Women largely not recognised as farmers.

Land Reform

- Post-independence land reform focused on:
  - Abolition of system of feudal landlords (*zamindars*).
  - Tenancy reforms to transfer ‘land to the tiller.’
  - Redistribution of land via ‘ceiling’ on holdings.

Failure of Land Reform

- Land reform not successfully implemented in most states.
- No focus on gender equity.
- 2 million acres of land declared surplus but not yet distributed because of litigation /other reasons.
- Post-1991: pro-liberalisation agenda.
- Push for removal of land ceiling restrictions.
- No political will to implement land reform.
- Draft *Twelfth Five Year Plan* (2012-2017): does not mention land reform.

Recommendations for Govt. of India (1)

- Adopt a strong *human rights approach* in all laws/policies/programmes.
- Implement *human rights-based agrarian reform* => land redistribution + agricultural resources (including seeds), water, information, & access to markets.
- Adopt *urban reform measures* + provision of homestead land in urban areas.
- Provide *legal security of tenure* & recognise *collective rights*.
- Strengthen *National Land Reforms Council*.
- Strengthen *Public Distribution System (PDS)*.

Recommendations for Govt. of India (2)

- Accord women equal rights to land and other natural resources, property, housing, inheritance.
- Control real estate speculation.
- Repeal *Land Acquisition Act* (1894).
- Develop a comprehensive National Land Reform Policy.

Recommendations for Govt. of India (3)

- Implement good laws:
  - *Panchayat Act* (1996) & 73rd Amendment Act – devolves powers to local self governing bodies.
  - *Forest Rights Act* (2008).
  - Directives on joint registration of land – names of men & women.
  - *Hindu Succession Amendment Act 2005* - equal inheritance rights for men & women.
- Enforce:
  - International human rights law.
  - Concluding Observations of UN treaty bodies & Special Rapporteurs.

Recommendations for EU (1)

- Ensure strong human rights protection clause is included in the EU-India FTA.
- Call for *Human Rights Impact Assessments* to be conducted ex-ante and ex-post – for all trade & investment agreements (requested by European Parliament in November 2010).
- Call for implementation of guidelines proposed by Special Rapporteur on right to food regarding land acquisitions & the *UN Basic Principles and Guidelines on Development-based Evictions and Displacement*.

Recommendations for EU (2)

- Issue guidelines for European investors in India that ensure protection of human rights.
- EU and India should respect rights of urban and rural poor, and protect small farmers and informal workers.
- Use Universal Periodic Review (UPR) of India at the Human Rights Council (May 2012) to promote the realisation of human rights to food/land in India.

LAND POOLING/READJUSTMENT TOWN PLANNING SCHEMES, RELEVANCE & APPLICATION

LAND POOLING/READJUSTMENT

LAND POOLING/READJUSTMENT

Land pooling/Readjustment is a technique for promoting efficient, sustainable and equitable land development in the urban fringes.

In Land pooling, the land parcels owned by individuals or a group of owners legally consolidated by the transfer of ownership rights to the designated land pooling agency which transfer the ownership of the part of the land back to the land owners for undertaking development for such areas

The concept of land readjustment has been used in various countries of the world for at least two hundred years.
Land readjustment works best when implemented in small to medium-size areas.

IMPORTANCE OF LAND POOLING

- Land is scarce in most Indian cities, especially metros.
- However, there are various parts of cities that are not efficiently developed and land usage is also not optimum. Apart from this, there are parts of cities that are not properly connected to the other parts.
- Through a land pooling policy, these areas are redeveloped so that more housing is created to accommodate the ever- increasing urban population.



ADVANTAGES & DISADVANTAGES OF LAND POOLING

• ADVANTAGES

- All the land, except whatever is needed for infrastructure development and social amenities, remains with the original owner. The development agency plays a limited role in ensuring planned urban growth.
- The increment in land value resulting from the development accrues to the original owner whenever the land is sold and developed for urban use. Thus the benefit of development goes to the original owner instead of the development agency.
- The original owner is not displaced in the process of land development and continues to enjoy access to the land resource. Thus the negative impact of the process of urbanization on farmers (original owners) is minimized.

• DISADVANTAGES

- This method is time consuming, since the procedure prescribed for preparation and implementation of such land pooling or readjustment schemes is unduly complicated and cumbersome.
- Betterment charges are assessed at the beginning of the land pooling or readjustment scheme preparation. Due to the inordinate delays in finalizing schemes, the betterment charges levied on finalization of the scheme do not meet the cost of the infrastructure provided.



LAND POOLING POLICY- DELHI




LAND POOLING POLICY- DELHI

For last six decades, Delhi's population has grown 10 folds to calculate 1.7 crore & According to the reports 60 lakh more people will add to the existing figures till 2021.

This needs additional land, covering 50,000–60,000 acres, as well as strong financial guarantee from government. As a matter of fact direct acquisition of land is not possible due to continuously increasing price as well as land owners always complaint for less compensation. In order to make way for this difficult situation, government has brought up land pooling policies to boost faster development.


Land pooling policy, approved by the authority removes the bottleneck of the land acquisition of DDA at government fixes prices



LAND POOLED BY DDA

There are two basic types of Land Pooling which have been announced so far:

- **20 hectares and above where 60% of land would be returned to the land owner**



BENEFITS OF LAND POOLING POLICY

▪**End of Land Acquisition Policy-** One of the most significant factor why LPP is necessary is because it would end the decades old land acquisition system. What this will do is prevent the ever increasing price of lands due to acquisition policy. The transparency is far below standard and the compensations are unfair to the farmers.

▪**Freedom to Public- Private sector–** DDA would only work as a caretaker/facilitator to this policy that would give the public private sector a chance to boom its relationship and hence enhance the development. No interference would give the private sectors ample freedom to develop infra within the rules set by the law.

▪**Development in NCR-** There is a 10 fold increase in population of Delhi in the past half century, which has increased the use of land. Due to its expansion Delhi needs to sort out a plan to make use of its neighboring villages' land. These land of villages like Dwarka,Narela, Bawana etc would get a standard way of development.







BENEFITS OF LAND POOLING POLICY

- **Ample Employment opportunities-** During the tenure of the development of LLP, it would provide home to more than 10 million households. This would vastly increase employment opportunities for every class of people who are related to the construction sector. It would help in the economic boom as well since there are many chances the foreign investments would be playing a key role in providing infra.

- **Revenues though tax-** It would be a very profitable venture for both the government as well as the owner of the land. The owner gets an opportunity to recover incurred cost and land as well. LPP would make for an accurate land registration system which would significantly increase public revenues from property taxes.

- **Revoke struggling real estate market–** The **Land Pooling Policy** would give real estate market a chance to re-establish itself. Land market is down, which is a hindrance to a nation. LPP would bring people back to real estate.





Adding to these benefits, many of the most developed cities has stick to the LPP mode of development and it has shown tremendous results. In India too, the states such as Gujarat, Andhra Pradesh etc have been pioneers to


TOWN PLANNING SCHEMES

TOWN PLANNING SCHEMES


Town Planning scheme (TPS) is also similar as Land pooling and Re-adjustment method. Through this method, the public planning agency or development authority temporarily pool together a group of landowners for the purpose of planning, under the aegis of the state-level town or urban planning act. There is no acquisition or transfer of ownership involved, issues pertaining towards compensation are avoided.

A master plan of the area is prepared, laying out the roads and plots for social amenities.

The remaining land is reconstituted into final plots for the original owners.

The size of the final plot is in proportion to the size of the original plot, and its location is as close as possible to the original plot. A betterment charge based on the cost of the infrastructure proposed to be provided is levied on the landowners.

Infrastructure is then provided utilizing these funds.



AHMEDABAD


- Ahmedabad is the city in Gujarat, which is the third Most urbanized State with 37.35 % of Urban Population as against 27.78 % of India, with 167 Urban Local Bodies

- Ahmedabad is 7th largest Urban Agglomeration in India, and third Fastest Growing Cities in the World

Ahmedabad that is a livable, environmentally sustainable and efficient city for all its citizens; a city with robust social and physical infrastructure and a distinct identity; a globally preferred investment destination



PLANNING






Figure 2.2: Land Use in AUDA Area (1997)

The Ahmedabad concept of development is in 2 tiers:

- Macro Level planning (City Level)
- Micro Level planning (Area Level)

OBJECTIVES

- Enhance accessibility
- Protect the vulnerable
- Accommodate and direct growth
- Protect Heritage assets
- Promote economic development

PROCEDURE OF TOWN PLANNING SCHEME:


- Draft Town Planning Scheme
- Sanction of Draft Town Planning Scheme by State Govt.
- Preliminary Scheme (Contains Physical Planning)
- Final Scheme (Contains Fiscal



THE CONCEPT – TOWN PLANNING SCHEME

Town Planning Scheme may be prepared for any land which
is:

- In the course of development
- Likely to be used for residential or commercial or industrial or for building purposes
- Already built upon




Land developed by:

- Appropriating portion of the land from the original land
- Providing regular shaped plots with proper access

Town planning schemes includes:

- Laying out or relaying out of land
- Lay-out of new streets or roads, bridges and underpass
- Reservation of land for roads, open spaces, gardens, recreation grounds, schools, markets, green-belts, dairies, transport facilities, public purposes of all kinds
- Laying of Water Supply, Drainage and Lighting
- Preservation of historical or national interest or natural beauty, and of buildings actually used for religious purposes





AIM OF TPS

- Walled city- to conserve Heritage
- Central Business District- to create distinct identity of the city
- Transit Corridor and High Density Zone- Land-use Transport Integration
- R-AH Zone- to promote Affordable Housing
- Prime Agriculture Zone- to conserve Double Cropped Land
- Logistics and Knowledge Zones- for Special requirements

PHYSICAL PLANNING OF THE TPS

▪Delineation of Town Planning Scheme Area





▪Superimposing DP Road Network


Roads proposed in the Sanctioned DP are over

▪Original Plot Remarking

Each survey no. is given a separate original plot no. (OP no.) Value of the OP is assessed on the basis







▪Preparation of Neighbourhood level Road Network

Town Planning Scheme Roads proposed in accordance with the adjoining Town Planning Scheme Road Network.



▪Demarcation of Public Purpose



▪Reconstitution of Final






FISCAL PLANNING

▪Original Plot Value

Original Plot Value has been derived from last 5 years Sales records from the Date of Declaration of Intention




▪Semi Final Value

Semi Final Value is a value of Final Plot allotted on respective Original Plot



▪Final Plot





INFRASTRUCTURE THROUGH TOWN PLANNING SCHEME

Regional Level Infrastructure:

- 76 km. long and 60 mts. wide Sardar Patel Ring Road

City Level Infrastructure Land for

- Socially and Economically Weaker Section People
- Water Supply
- Sewerage
- Recreational
- Social Infrastructure etc.
- City Level Road Network

Neighbourhood Level Infrastructure


- Water Supply Network
- Sewerage Network
- Neighbourhood level Recreational
- Neighbourhood level Road Network
- Neighbourhood level Lighting
- Land for Civic Center and Neighbor Center (for Public Utility Services)
- Land for Educational Purposes







Nandanvan



Gokul



Varjnagari



Murlidhar



Vastrapur



Sardarnagar



Ranip



Gopal







RELEVANCE OF TOWN PLANNING SCHEME IN AHMEDABAD

- Promotes planned development.
- Equal opportunity to everyone to play the role of a land developer
- Self Financing Mechanism was introduced
- Flexible Mechanism for Planning and Resource Mobilization
- Increases the build ability of the Plots
- All Plots having Accessibility and Services
- Hierarchical Road Networks within City and better linkages with Region
- Improved Environment (for air quality from 4th to 43rd polluting city in India)
- Preservation of Heritage and elements of Nature Beauty
- Owners/ farmers are benefitted with service plots which results in better livelihood

Maharashtra Regional Town Planning Act (1966)

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance

It started with…

Bombay Act 1915

for Bombay state

today geographical boundary of Gujarat & Maharashtra

It provides for:

1. Preparation of Town Planning Schemes
2. Recovery of betterment contribution from benefitted owners of land

It started with…

Bombay Act 1915

for Bombay state

today geographical boundary of Gujarat & Maharashtra

Shortcomings:

Piecemeal planning, no relation with adjoining areas

this lead to inevitable enactment of…

Bombay Town Planning Act 1954

for Bombay, Saurashtra, Kutch, Gujarat area, Vidarbha & Marathwada

- **Concept of Development Plan was introduced**
- **TP remained the main planning instrument for implementation of DP**

concept of regional planning was realized...

Maharashtra Regional Town Planning Act 1966

Model act for Maharashtra state based on comprehensive planning theory

- **Regulated development in urban areas**
- **And in areas having potential of becoming urbanized**

Maharashtra Regional Town Planning Act 1966

The participants:

1. Regional Planning Board – Director of Town Planning, Town planning officer, others appointed by the state from local authorities and other persons with special knowledge or practical experience.
2. Regional Planning Committee – Advisory body
3. Planning Authority – local authority, a special planning authority
4. State Government
5. Public

Maharashtra Regional Town Planning Act 1966

Objectives of enactment of MRTP Act:

- Planning development in "regions"
- Constitution of Regional Planning Board
- Better provision for preparation of DP & TP
- To provide for creation of new towns by means of DA
- To make provisions for the compulsory acquisition of land required for public

  purposes in respect of the plans


Salient Features:

- Provisions for RP, DP & TP
- And Implementation schemes : Land acqtn., TDR, Plot reconstitution
- Finance, accounts & audit and Governance for plan enforcement are also available under this act

Maharashtra Regional Town Planning Act 1966

The 3 scales:

1. Regional Plan
2. Development Plan
3. Town Planning Scheme



Maharashtra Regional Town Planning Act 1966

Regional Planning contents & scale:

- Allocation of land for different uses
- Reservation of areas for open spaces, recreation etc.
- Transport & communication
- Public utilities & amenities like water supply, drainage etc.
- Reservation of sites for green field development
- Preservation, conservation & development of areas of natural scenery, forest etc.
- Heritage preservation
- Areas for military & defence purposes
- Prevention of erosion & afforestation, reforestation & other environmental issues
- Proposals for irrigation, water supply, flood control etc.
- Distribution of population

Generally adopted Graphic scale – 1:80,000 or 1:1,00,000

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance



Establishment of region

By State Government

Notification in *official gazette*

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance



Constitution of Regional Planning Board

By State Government

Notification in *official gazette*

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance




Survey of Region

By Regional Planning Board

No prescribed time limit, but as the State govt. may determine

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance




Preparation of Draft Regional Plan By Regional Planning Board

Notification in *official gazette;* Copies available for sale to public

Suggestions &Objections invited before such date not less than 4 months

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance




Modifications

By Regional Planning Committee

Reasonable opportunity to all persons affected of being heard

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance




Submissions to State Government

By Regional Planning Board

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance



Publication of 'Final Regional plan' & Date of operation

By State Government


Available for sale to public

Plan would come into operation not before 60 days from publication

Restriction on change of user or development*

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance



Revision of Regional Plan

By State Government

Not earlier than 10 years

May follow the same process right from 'Establishment of region'

Maharashtra Regional Town Planning Act 1966


Development Plan contents & scale:

- Allocation of land for different uses
- Reservation of areas for open spaces, recreation etc.
- Transport & communication
- Public utilities & amenities like water supply, drainage etc.
- Service industries, industrial estates etc.
- Preservation, conservation & development of areas of natural scenery, forest etc.
- Heritage preservation
- Proposals for irrigation, water supply, flood control etc.
- The filling up or reclamation of low lying, swampy or unhealthy araes, or levelling up of land
- Development control regulations

Generally adopted Graphic scale – 1:8,000 or 1:10,000

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance



Declaration of the intention to prepare DP


By Planning Authority

Notification in *official gazette*

Restriction on development

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance



Declaration of the intention to prepare DP

By Planning Authority


Notification in *official gazette*

Restriction on development

Suggestions & Objections invited from public not before 60 days

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance



Survey & preparation of existing Land-use map


By Planning Authority

Not later then 6 months from the date of declaration of intention

Time can be extended by Sate govt.

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance



Preparation of draft Development Plan


By Planning Authority

Not later then 24 months from the date of declaration of intention

Notification in *official gazette*

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance



Preparation of draft Development Plan

By Planning Authority


Not later then 24 months from the date of declaration of intention

Notification in *official gazette*

Suggestion & Objections invited with in 60 days from the notification

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance



Modifications in the draft DP


By Planning Committee

The affected are given a reasonable opportunity of being heard

&submit report to Planning Authority within 2 months

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance



Modifications in the draft DP


By Planning Authority

Including modifications in draft DP within 3 months of receipt from PC

Notification in Official Gazette

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance




Suggestions & Objections invited from public

By Planning Authority

Within 60 days from date of notice

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance




Submission to the State Government

By Planning Authority

Within 12 months from the date of publication of notice in the official gazette, regarding its preparation (may be extended but not more than 24 months)

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance



Sanction of plan


By State Government

Within 12 months from the date of receipt of plan

Notification in Official Gazette; inviting objections (if any) within 60 days

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance



Final Development Plan & Acquiring of land

By State Govt. & Planning Authority resp.

Final DP would come into operation after 1 month from its publication

Acquiring of land within 10 years from the date of operation


Revision within 20 years from the date of operation

Contents of Draft Town Planning Scheme

1. Ownership, area and tenure of original land holdings.
2. Details of reservation, acquisition or allotment of land.
3. Extent and boundaries where plot reconstitution is required.
4. Total cost estimations.
5. Allotment of final plots to owner and transfer of ownership.

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance




Declaration of intention

Notification in *official gazette within 30 days*

Restriction on development

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance




Suggestions & Objections invited from public

Within 30 days from date of notice

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance



Preparation & Publication of Draft scheme


Within 12 months of declaration

Restriction on development

Copies Draft TPS available for inspection or sale

Maharashtra Regional Town Planning Act 1966

evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance




Appointment of Arbitrator

Within 1 month of sanction of draft TPS

By publishing in official gazette

Maharashtra Regional Town Planning Act 1966


evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance



Suggestions & Objections invited

Maharashtra Regional Town Planning Act 1966


evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance



Submission Final Scheme to State Govt.

Maharashtra Regional Town Planning Act 1966


evolution . participants . objectives . stages . regional plan . development plan . town planning scheme . land management options . funding & finance



Sanction of Final TP Scheme

Within 4 months of submission

Maharashtra Regional Town Planning Act 1966



Enforcement of Scheme

Maharashtra Regional Town Planning Act 1966

Land management options:

1. Land acquisition
2. Transferable Development Rights (TDR)
3. Plot reconstitution method

Maharashtra Regional Town Planning Act 1966

Planning and Development Funds consist of:

1. Grants from National & State Govt. and any other agencies.
2. Budget allocated to the planning authority.
3. Development charges and fees.
4. Betterment charges.
5. Development permission charges.
6. Loans.

Maharashtra Regional Town Planning Act 1966

Shortcomings:

- No definite time limit prescribed for the preparation of DP by the planning authority
- Reservations for public use on private lands remains on paper itself
- DPs too idealistic, out of implementing capacity
- Act casts obligation on the planning authority to prepare a DP, but no similar obligation to implement it
- No time limit prescribed for TPS

Maharashtra Regional Town Planning Act 1966

References:

- The Maharashtra Regional & Town Planning Act, 1966, R.K. Pillai
- **Study of 'Maharashtra Regional Town Planning Act':** Amendments concerning TP Schemes (special emphasis on Pune Region), *Ar. Omkar Parishwad, 2011*



"If you fail to plan,
you are planning to fail".